

JIANGSU JUXIN PETROLEUM STEEL PIPE CO., LTD

No.1 DONGZHUANG ROAD, GUANGLING INDUSTRIAL PARK, YANGZHOU, JIANGSU, CHINA

Tel: +86-514-87209333 Fax: +86-514-87209555

Invoice

订单号/PO No.:

发票号/Invoice No.: JXWMC-25-12-31 rev 1

日期/Date: 31st Dec, 2025

买方/The Buyers: GAS Entec CO.Ltd.

地址/Address: 616,6th floor, Islamic hospital, Mutah street Aqaba, Jordan

电话/Tel: +82 51 714 3413

电子邮件/Email: syshin@gasentec.com

This Proforma Invoice is made by and between the Buyers and the Sellers; whereby the Buyers agree to buy and the Sellers agree to sell the under mentioned goods on the terms and conditions stated below:

Item	Description	Dimension(mm)	Quantity	Weight (t)	FOB Shanghai Rate	Amount (USD)
1	LSAW steel pipe piles	S355J0, Φ1016*25*L	19.7m	12.036	888	10687.74
2	LSAW steel pipe piles	S355J0, Φ1220*25*L	920.013	677.79	888	601877.23
3	Pile shoe(welded)	S355J0, Φ1220*35*L	16.5	16.876	995	16791.38
4	Shear key (unwelded)	S355J0, 25*30mm bar, 3 runs/pile, 33 runs		130.00 m	26	3380.00
4	Coating	PFP Zone 6.05 m from top of pile PPG SIGMAPRIME 200 75um, Color: grey		255.00 m ²	14.5	3697.50
5	Coating	Splash Zone MSL=0-(+2.5m), PPG SIGMACOVER 850 1000 μm, PPG SIGMADUR 550 50 μm, Color: RAL7038		110.00 m ²	30	3300.00
6	Coating	General Area, remain coating length, PPG SIGMACOVER 850 500 μm, Color: RAL7035		1280.00 m ²	20	25600.00
7	steel plate(unwelded)	Q235B, Φ1160*4mm round steel plate with 4 Φ50mm holes		11.00 pcs	28	308.00
	Total					665641.86

JIANGSU JUXIN PETROLEUM STEEL PIPE CO., LTD

No.1 DONGZHUANG ROAD, GUANGLING INDUSTRIAL PARK, YANGZHOU, JIANGSU, CHINA

Tel: +86-514-87209333 Fax: +86-514-87209555

	Total Amount (FOB SHANGHAI Port)	665641.86
	40% Downpayment of Total Amount (FOB SHANGHAI Port)	266256.74
	SAY IN WORDS (USD) :TWO HUDNRED SIXTY SIX THOUSAND TWO HUNDRED FIFTY SIX AND CENTS SEVENTY FOUR ONLY	
Remarks	<p>Raw material / plate to be sourced / compliant to EN10025 S355J0.</p> <p>All piles to be delivered to Shanghai Port in 75 days after the confirmation of PO and Segmented length list of steel pipe pile</p> <p>New LSAW steel pipe shall be manufactured as per requirements of EN10219 and as per SPEC/PR</p> <p>All pipes to be tested 100% VT and UT In -house c/w VT and UT reports on all weld seams; Weld VT/UT inspection acceptance criteria per EN ISO 15609-1 and ISO 17640(2016) class B ;</p> <p>All weld to be tested 100% UT and VT by third party.; PAUT has not been involved.</p> <p>Shear key: 3 runs of S355J0, 25*30mm bar weld internal of pile from 420mm of pile top . Interval 400mm for each shear key.</p> <p>Round steel plate: Φ1160*4mm round steel plate with 4 Φ50mm holes, not welded, delivery as a loose part.</p> <p>Quantity tolerance:-0%/+0%;</p> <p>The steel pipe piles shall be fabricated to the tolerances specified in EN10219 and customer's requirement;</p> <p>When welding steel circular piles the vertical seams in adjoining section shall be offset a minimum of 300mm.</p> <p>Coating system: PFP Zone 6.05 m from top of pile PPG SIGMAPRIME 200 75um, Color: grey,</p> <p style="padding-left: 40px;">Splash Zone MSL=0-(+2.5m), PPG SIGMACOVER 850 1000 μ m, PPG SIGMADUR 550 50 μ m, Color: RAL7038</p> <p style="padding-left: 40px;">General Area, remain coating length, PPG SIGMACOVER 850 500 μ m,Color: RAL7035</p> <p style="padding-left: 40px;">200mmfrom pile section top/bottom (site weld area) will be coated with 20 μ m sigamaweld 165</p> <p style="padding-left: 40px;">Sand blast class ISO 8501-1 Class 2.5</p> <p>2 off EN1492 Slings and 50mm protective Nylon rope every 6 m for coated area, pre-slung (chocked) before shipping</p> <p>Submittal Documents:ITP, WPS/PQR, Welder Qualifications, Shop Drawing ,Manufacturing Schedule, VT/UT Inspectors certificates, Steel Plate MTC (MTC in accordance EN10204 3.1), Welding Material MTC, etc.</p> <p>Each pipe to be clearly marked on both ends of inside of the pipe showing: Size, Length, Grade, Pipe number only. All pipes to be stenciled in a permanent way so that the markings do not come off in rain or fade out.</p>	

Payment Term: 40% of total value be paid in 3 working days after receiving same amount AP bond and 10% performance bond. Balance be paid in 7 working days at sight of B/L copy and no later than 7 days before vessel arrival. 40% AP bond and 10% performance bond valid to cargo ready for delivery at factory.

Beneficiary : JIANGSU JUXIN PETROLEUM STEEL PIPE CO., LTD

JIANGSU JUXIN PETROLEUM STEEL PIPE CO., LTD

No.1 DONGZHUANG ROAD, GUANGLING INDUSTRIAL PARK, YANGZHOU, JIANGSU, CHINA

Tel: +86-514-87209333 Fax: +86-514-87209555

Bank Name : BANK OF NANJING

Address : BLDG 2, HUACHENG PLAZA, NO.456 WHENCHANG W.ROAD, YANGZHOU JIANGSU CHINA

Account No. : 08011420030001130

Swift Code : NJCBCNBNXXX

FOR BUYER

GAS ENTEC CO.LTD.

FOR SELLER

江苏巨鑫石油钢管有限公司
JIANGSU JUXIN PETROLEUM STEEL PIPE CO., LTD

Handwritten signature

JD